


REGION NO.	STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
8	S.D.	2017-012	1	23
COVER				

**2017-012**  
**2ND STREET PEDESTRIAN CALMER PROJECT**  
**CITY OF YANKTON, SD**




YANKTON PROJECT SITE

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 ESTIMATE OF QUANTITIES
- 3-4 GENERAL NOTES
- 5 TRAFFIC CONTROL
- 6 EROSION CONTROL
- 7-9 SWPPP
- 10-11 CEDAR STREET LAYOUT
- 12-13 DOUGLAS AVE. LAYOUT
- 14-15 CAPITAL STREET LAYOUT
- 16-23 DETAILS

**LEGEND**

- POWER POLE
- TELEPHONE BOX
- CURB INLET
- SANITARY SEWER MANHOLE
- STORM SEWER MANHOLE
- VALVE
- PROPOSED VALVE
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- PROPERTY LINE
- SANITARY SEWER
- STREET CENTERLINE
- CURB
- WATER
- BURIED CABLE TV
- BURIED GAS LINE
- BURIED ELECTRIC LINE
- BURIED TELEPHONE LINE
- EXISTING STORM SEWER
- WORK LIMITS - AS PER CROSS SECTIONS



**PROJECT SITE 2017-012**  
 2ND STREET CALMER PROJECT  
 CITY OF YANKTON, SOUTH DAKOTA  
 SW 1/4 SEC 18 T93N, R55W



# ESTIMATE OF QUANTITIES

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	2	23
Quantities	6/7/2017	

BID ITEM NUMBER                      ITEM                                      QUANTITY                      UNIT

Removals and Grading				
1	Mobilization	1		LS
2	Saw Existing Concrete	1575		LF
3	Saw Existing Asphalt	204		LF
4	Removal of Concrete Pavement	3001		SY
5	Removal of Asphalt Pavement	1195		SY
6	Removal of Curb & Gutter	732		LF
7	Unclassified Excavation (See Note on Sheet 3)	1		LS
8	Undercutting	50		CY
9	Water for Embankment or Granular Material	10		KGal
Erosion Control				
10	Inlet Sediment Control	14		EA
Traffic Control				
11	Traffic Control	752		UNITS
12	Traffic Control Miscellaneous	1		LS
Surfacing				
13	8" P.C.C. Pavement	2148		SY
14	Insert Steel Bars in P.C.C. Pavement	350		EA
15	8" Concrete Fillet Section	2381		SF
16	6" Approach P.C.C. Pavement	830		SF
17	6" Concrete Sidewalk	7846		SF
18	6" Colored Concrete Sidewalk	7092		SF
19	Detectable Warning Panel	336		SF
20	Concrete Curb and Gutter (B68)	1200		LF
21	6" Aggregate Base Course (See Note on Sheet 5)	2746		SY
STORM SEWER				
22	Type B Inlet with R-3067 Inlet frame, grate & curb box	6		EA
23	R-3067 Inlet frame, grate & curb box	3		EA
24	F&I 18" RCP CL 3 (round)	186		LF
25	F&I 15" RCP CL3 (round)	8		LF
26	Storm Sewer Pipe bedding material	186		LF
27	Core existing Inlet	5		EA
28	2'X2' Area Drain (See Note on Sheet 12)	1		EA
29	2'X2' Junction Box with MH rim & lid (See Note on Sheet 12)	1		EA
30	Install 3'x3' concrete lid on existing inlet	2		EA

### TABLE OF 6" CONCRETE APPROACH / DRIVEWAY PAVEMENT

LOCATION	(6" CONC.) QUANTITY (SF)
CAPITAL STREET	630
MISCELLANEOUS	200
<b>TOTAL</b>	<b>830 (SF)</b>

### TABLE OF CONCRETE CURB & GUTTER REMOVAL

LOCATION	REMOVE QUANTITY (LF)
CEDAR STREET	142'
DOUGLAS AVENUE	344'
CAPITAL STREET	196'
MISC.	50'
<b>TOTAL</b>	<b>732' (LF)</b>

### TABLE OF CONCRETE CURB & GUTTER B68

LOCATION	INSTALL QUANTITY (LF)
CEDAR STREET	231'
DOUGLAS AVENUE	559'
CAPITAL STREET	360'
MISC.	50'
<b>TOTAL</b>	<b>1200' (LF)</b>

### TABLE OF REMOVE ASPHALT PAVEMENT

LOCATION	QUANTITY (SY)
DOUGLAS AVE.	605
CAPITAL STREET	590
<b>TOTAL</b>	<b>1195 (SY)</b>

### TABLE OF 8" PCC PAVEMENT

LOCATION	QUANTITY (SY)
CEDAR STREET	399
DOUGLAS AVE.	926
CAPITAL STREET	723
MISC.	100
<b>TOTAL</b>	<b>2148 (SY)</b>

### TABLE OF 6" SIDEWALK PLACEMENT

LOCATION	QUANTITY (SF)
CEDAR STREET	1867
DOUGLAS AVE.	2989
CAPITAL STREET	2790
MISC.	200
<b>TOTAL</b>	<b>7846 (SF)</b>

### TABLE OF REMOVE CONCRETE PAVEMENT

LOCATION	QUANTITY (SY)
CEDAR STREET	874
DOUGLAS AVE.	1194
CAPITAL STREET	883
MISC.	50
<b>TOTAL</b>	<b>3001 (SY)</b>

### TABLE OF CONCRETE FILLET SECTION

LOCATION	QUANTITY (SF)
CEDAR STREET	652
DOUGLAS AVE.	966
CAPITAL STREET	663
MISC.	100
<b>TOTAL</b>	<b>2381 (SF)</b>

### TABLE OF 6" COLORED SIDEWALK PLACEMENT

LOCATION	QUANTITY (SF)
CEDAR STREET	1867
DOUGLAS AVE.	2815
CAPITAL STREET	2210
MISC.	200
<b>TOTAL</b>	<b>7092 (SF)</b>

### TABLE OF STEEL BAR INSERTION

LOCATION	QUANTITY (EA)
CEDAR STREET	100
DOUGLAS AVE.	110
CAPITAL STREET	120
MISC.	20
<b>TOTAL</b>	<b>350 (EA)</b>

# NOTES

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	3	23
NOTES	6/7/2017	

**SPECIFICATIONS TO BE USED**

City of Yankton Standard Specifications and the Standard Specifications for Roads and Bridges 2004 Edition and Required Provisions, Supplemental Specifications, and/or Special Provisions as included in the Proposal.

**UTILITIES**

Location and protection of all underground utilities is the Contractors responsibility. The Contractor will be required to coordinate work with the utility companies. Existing utilities and service lines that coincide with proposed underground main locations are to be located in advance by the contractor such that proposed underground mains can be adjusted to avoid conflict.

Utility locations are coordinated by calling: 1-800-781-7474 (One Call)

**SEQUENCE OF OPERATIONS**

The Contractor shall use the following sequence of operations that are listed on the traffic control sheets unless an alternate is approved by the Engineer. An alternate sequence must be submitted in writing a minimum of one week prior to the preconstruction meeting.

The Contractor will need to get an approved Phasing & Traffic Control plan that maintains traffic on 2<sup>nd</sup> Street at all times. The contractor will not be allowed to remove concrete on all the intersections at one time. Once started, each intersection will need to be substantially complete before the contractor can move on to the next intersection. The contractor should get approval from the engineer prior to starting removals on each intersection.

The contractor is to coordinate their work, with the City of Yankton, for the installation of street lights and bases.

All trenches are to be backfilled, compacted and covered with service gravel on the same day the pipe is laid. Aggregate Base Course will be used in lieu of Service Gravel as directed by the engineer to temporarily re-open portions of streets after the pavement is removed.

**REMOVAL OF EXISTING CONCRETE PAVEMENT**

Payment for concrete removal is included in the contract unit price per square yard for "Removal of Concrete Pavement". Payment shall be at the contract unit price per square yard, regardless of variations in thickness. Joints shall be sawed wherever existing concrete is to be connected to new construction.

When asphalt is laid over concrete pavement, removal of the asphalt surfacing shall be incidental to the unit price for "Removal of Concrete Pavement".

**REMOVAL OF EXISTING ASPHALT PAVEMENT**

Payment for asphalt mat removal is included in the contract unit price per square yard for "Removal of Asphalt Concrete". Payment shall be at the contract unit price per square yard, regardless of variations in thickness.

**6" CONCRETE SIDEWALK**

Concrete sidewalk shall be constructed in accordance with Section 651 of Standard Specifications. Base Course material, two (2) inches thick, shall be placed beneath the sidewalk.

**GENERAL MAINTENANCE OF TRAFFIC**

1. Storage of vehicles and equipment shall be as near the right-of-way as possible. Contractor's employees should mobilize at a location off the right-of-way and arrive at the work sites in a minimum number of vehicles necessary to perform the work. Indiscriminate driving

and parking of vehicles within the right-of-way will not be permitted. Any damage to the vegetation, surfacing, embankment, delineators and existing signs resulting from such indiscriminate use shall be repaired and/or restored by the Contractor, at no expense to the City, and to the satisfaction of the Engineer.

2. The Contractor shall designate an employee whose responsibility is the maintenance of traffic, 24 hours a day and 7 days a week. The person so designated must have training and experience in the field of construction traffic control and be knowledgeable about the Manual on Uniform Traffic Control Devices (MUTCD). The cost of the traffic control person shall be incidental to the contract lump sum price for Traffic Control Miscellaneous. The employee selected must be approved by the Engineer. The name, phone number, and location of person(s) shall be provided to the county sheriff's department and the local police department. Road closure and barricading shall immediately be reported to the local police department by the Contractor. Local police department phone number 605-668-5210

3. Work activities during non-daylight hours are subject to prior approval.

4. The contractor shall maintain traffic control every day. The contractor shall have \$200.00 per day deducted from the contract for each day that traffic control is not maintained. If traffic control is not in place when the contractor begins work which requires traffic control, payment for bid item "Traffic Control" will be reduced by 50%.

5. The Contractor shall notify the City of Yankton Street Department prior to construction to enable the city forces to remove and salvage existing traffic control signs. City of Yankton Street Dept. number 605-668-5211

**WASTE DISPOSAL SITE**

Contractor shall dispose of broken concrete and asphalt generated by this project at the city stockpile site located at 23rd and Kellen Gross Drive. No tipping fee will be assessed to Contractor for broken concrete and asphalt disposed of at this site. Concrete and asphalt is to be kept separate from earth material during the removal process. Concrete and asphalt may be mixed.

Asphalt contaminated with soil during the removal process or concrete containing reinforcing steel or contaminated with soil must be disposed of at the Yankton rubble site, 23rd and Kellen Gross Drive. Disposal fees shall be the Contractors responsibility, and considered incidental to other pay items.

The Contractor will be required to use a state permitted solid waste disposal facility. The Contractor can obtain a list of permitted solid waste disposal facilities in the Yankton area or discuss proper disposal of construction and demolition debris by contacting Waste Management Program at 1-(605)-773-3153.

Construction/demolition debris may not be disposed of within the ROW.

**UNCLASSIFIED EXCAVATION**

Unclassified Excavation will be paid for on a lump sum basis. The bid item for "Unclassified Excavation" shall include removing the existing material to a depth of 6 inches below the new road surface shown on the typical sections. Estimated quantities in cubic yards are shown below. These estimates are based on the assumption of 8 inches of existing Concrete Pavement being removed separately.

Estimate of 345 cu yds. of removal. Excess material is to be hauled to City property located at 33rd and Douglas Ave.

**GENERAL NOTES**

The Contractor will be required to raze, remove and dispose of all buildings and foundations, structures, fences, advertising signs, and other obstructions of which any portion are on the

right-of-way or Temporary Easements except Utilities and those for which other provisions have been made for removal, in accordance with Section 110 of the Standard Specifications.

The removal and disposal of all buildings, foundations and other obstructions not removed under Incidental Work or on a unit basis shall be considered as subsidiary work to the other Contract Items and no separate payment will be made for their removal and disposal.

**"8" NONREINFORCED CONCRETE PAVEMENT**

The Coarse Aggregate shall be Crushed Ledge Rock.

The fine aggregates may require screening as determined by the Engineer.

The concrete mix shall be Class A40 concrete paving mix when slip form construction is used and Class A45 when formed construction is used.

Portland Cement Concrete Pavement shall have a minimum cement content of 600 pounds per cubic yard and Class C Fly Ash will be excluded.

In lieu of an automatic subgrader operating from a preset line, a motor grader or other suitable equipment may be used to bring the base course to final grade prior to placement of the concrete.

A construction joint shall be sawed whenever new concrete pavement is placed adjacent to existing concrete pavement.

There will be no direct payment for trimming of the Base Course for PCC pavement. The trimming will be considered incidental to the related items required for PCC pavement. Trimming shall be performed as required by Section 380.3c of the Standard Specifications.

An automated paving machine such as a Bidwell, or equivalent, shall be required for main line paving. An air or vibratory screed will not be allowed for main line paving.

**PEDESTRIAN TRAFFIC**

The Contractor will be required to maintain pedestrian access during construction. Pedestrian access shall be ADA accessible and shall conform to the Manual on Uniform Traffic Control Devices 2009 edition. Access can either be maintained on concrete sidewalk or on a temporary boardwalk. This work may include but is not limited to sawing existing sidewalk to leave half in place, staging sidewalk removal and construction to maintain access, installing safety fence around work areas, and construction and removal of temporary boardwalk. The Contractor shall determine the actual location of temporary access during construction and shall be approved by the Engineer. Payment for all work and associated materials shall be incidental to the contract lump sum price for "Traffic Control Miscellaneous".

**ACCEPTANCE TESTING**

The City will be responsible for taking the first acceptance test and a backup test if required. All subsequent tests required due to failures will be paid by the Contractor by deducting the cost from the pay request.

**CONCRETE JOINT SEALER**

Concrete Joint Sealer shall be hot poured elastic joint sealer and shall conform to section 870 of the Standard Specifications. Payment for concrete joint sealer shall be incidental to PCC Pavement and no separate payment shall be made.

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	4	23
NOTES	6/7/2017	

# NOTES

## DEWATERING AND EROSION CONTROL

Pumping required for the removal of surface water from the work area and/or depressions will be considered incidental to other pay items and not paid for separately. The Contractor shall be responsible for obtaining the required erosion control permits from the South Dakota Department of Environment and Natural Resources.

## SITE MAINTENANCE

The Contractor is to keep the project site properly maintained and graded to drain storm water. No standing water is permitted on site. A penalty of \$500/day will be assessed each day standing water is not removed from site. All regulations pertaining to Storm Water Pollution Prevention will be enforced. Direct discharge of storm water into the storm sewer system is not acceptable.

## STEEL BAR INSTALLATION

The Contractor shall install Steel No. 5x24" epoxy coated deformed tie bars into drilled holes in the existing concrete pavement. An epoxy resin adhesive must be used to anchor steel bars in the drilled holes.

The steel bars shall be cut at the specified length by sawing and shall be free from burring or other deformations. Shearing will not be permitted.

Epoxy resin adhesive shall be of the type intended for horizontal applications, and shall conform to the requirements of ASTM C 881, Type 1, Grade 3 (equivalent to AASHTO M235, Type 1, Grade 3).

The diameter of the drilled holes in the existing concrete pavement for the steel bars shall not be less than 1/8 inch nor more than 3/8 inch greater than the overall diameter of the steel bar. Holes drilled into the existing concrete pavement shall be located at mid-depth of the slab and true and normal. The drilled holes shall be blown out with compressed air using a device that will reach to the back of the hole to ensure that all debris or loose material has been removed prior to epoxy injection.

Mix the epoxy resin as recommended by the manufacturer and apply by an injection method approved by the Engineer. If an epoxy pump is utilized, it shall be capable of metering the components at the manufacturers designated rate and be equipped with an automatic shut-off. The pump shall shut off when any of the components are not being metered at the designated rate. Fill the drilled holes 1/3 to 1/2 full of epoxy, or as recommended by the manufacturer, prior to insertion of the steel bar. Care shall be taken to prevent epoxy from running out of the horizontal holes prior to steel bar insertion. Rotate the steel bar during installation to eliminate voids and ensure complete bonding of the bar. Insertion of the bars by the dipping method will not be allowed.

Cost for the epoxy resin adhesive, steel bars, drilling of holes, applying the adhesives, installing the steel bars into the drilled holes and all other items incidental to the installation of the steel bars shall be included in the contract unit price per each for "Install Steel Bar in Concrete Pavement".

## INCIDENTAL WORK

All salvageable materials shall be taken out intact and stockpiled within the right-of-way to the satisfaction of the Engineer. The Contractor shall perform salvage operations in a manner that will prevent damage to the salvageable materials.

Salvable materials will be picked up by the City.

All concrete removed from the existing structures and other disposable material shall be disposed of in accordance with the Notes Regarding Waste Disposal Site

## INLET SEDIMENT CONTROL

Refer to Standard Plates 734.21 AND 734.16 - Drop inlet sediment filters.


## COLORED CONCRETE SIDEWALK IN BOULEVARDS

The colored concrete sidewalks shall be colored per manufacturer recommendations. The color shall be determined by the City of Yankton. The contractor shall submit a sample piece of colored concrete to the Field Engineer for approval before placing the colored sidewalk for the boulevard. All costs for coloring shall be incidental to the contract unit price per square foot for the corresponding colored concrete sidewalk bid item.

Two coats of a non-yellowing acrylic curing and sealing compound shall be applied to the surface of the colored concrete. The curing and sealing compound shall be the product listed below or an equal approved by the Engineer.

DECRA-SEAL  
W.R. Meadows, Inc  
1-800-342-5976  
[www.wrmeadows.com](http://www.wrmeadows.com)

All cost for furnishing, handling, and applying the curing and sealing compound, including the materials, equipment, labor and incidentals necessary shall be incidental to the contract unit price per square foot for the corresponding colored concrete sidewalk bid item.




PROJECT AREA



SCALE: N.T.S.

# TRAFFIC CONTROL LAYOUT FOR REMOVALS & PAVING OPERATIONS

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	5	23
TRAFFIC CONTROL		6/7/2017



FOUR - 8' TYPE III BARRICADES  
FULL ROADWAY CLOSURE

**PEDESTRIAN TRAFFIC CONTROL**  
TRAFFIC CONTROL DEVICES FOR SIDEWALK CLOSURES AND PEDESTRIAN DETOURS SHALL BE PAID FOR UNDER TRAFFIC CONTROL MISC. (SDDOT STANDARD PLATE #634.33 MAY BE USED AS A GUIDE FOR THESE SITUATIONS, SHOWN ON SHEET 66)

ITEMIZED LIST FOR TRAFFIC CONTROL BID ITEM					
SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	SUB TOTAL
R11-2	48" x 30"	ROAD CLOSED	2	27	54
R11-4	60" x 30"	ROAD CLOSED LOCAL TRAFFIC ONLY	3	30	90
R3-1	24" x 24"	NO RIGHT TURN (SYMBOL)	2	15	30
R3-2	24" x 24"	NO LEFT TURN (SYMBOL)	2	15	30
W20-1	48" x 48"	ROAD WORK AHEAD	2	34	68
---	---	TYPE III BARRICADES	96 L.F.	5 UNITS/L.F.	480
				TOTAL	752

**NOTE:**  
USE TUBULAR MARKERS AS NEEDED TO DIRECT TRAFFIC THROUGH INTERSECTIONS UNDER CONSTRUCTION. (TRAFFIC CONTROL MISC. BID ITEM)

LIST OF OTHER TRAFFIC CONTROLS FOR ROAD CONSTRUCTION		
BID ITEM	DESCRIPTION	QUANTITY
TRAFFIC CONTROL MISC.	TYPE I & II BARRICADES, CONES, VERTICAL PANELS, DRUMS, BARRICADE WARNING LIGHTS, DELINEATORS, WATCHMAN, TUBULAR MARKERS, AND INSTALLATION OF CITY SIGNS.	LUMP SUM

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	6	23
EROSION CONTROL		6/7/2017

# EROSION CONTROL


## LEGEND

 INLET PROTECTION (TYPICAL) -SEE DETAIL SHEET 23

 PROJECT AREA



SCALE: N.T.S.



# SWPPP

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	7	23
SWPPP	6/7/2017	

## **STORM WATER POLLUTION PREVENTION PLAN**

*(The numbers right of the title headings are reference numbers to the GENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES)*

### ❖ **SITE DESCRIPTION (4.2 1)**

- **Project Limits:** See Title Sheet (4.2 1.b)
- **Project Description:** See Title Sheet (4.2 1.a.)
- **Site Map(s):** See Title Sheet and Plans (4.2 1.f. (1)-(6))
- **Major Soil Disturbing Activities** (check all that apply)
  - Clearing and grubbing
  - Excavation/borrow
  - Grading and shaping
  - Filling
  - Cutting and filling
  - Other (describe):
- **Total Project Area** 1.0 acres (4.2 1.b.)
- **Total Area To Be Disturbed** 0.5 acres (4.2 1.b.)
- **Existing Vegetative Cover (%)**
- **Soil Properties:** AASHTO Soil Classification (4.2 1. d.)
- **Name of Receiving Water Body/Bodies** Missouri River (4.2 1.e.)

### ❖ **ORDER OF CONSTRUCTION ACTIVITIES (4.2 1.c.)**

(Stabilization measures shall be initiated as soon as possible, but in no case later than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Initiation of final or temporary stabilization may exceed the 14-day limit if earth disturbing activities will be resumed within 21 days.)

- **Special sequencing requirements** (see sheet).
- **Install stabilized construction entrance(s).**
- **Install perimeter protection where runoff sheets from the site.**
- **Install channel and ditch bottom protection.**
- **Clearing and grubbing.**
- **Remove and store topsoil.**
- **Stabilize disturbed areas.**
- **Install utilities, storm sewers, curb and gutter.**
- **Install inlet and culvert protection after completing storm drainage and other utility installations.**
- **Complete final grading.**
- **Complete final paving and sealing of concrete.**
- **Complete traffic control installation and protection devices.**
- **Reseed areas disturbed by removal activities.**

### ❖ **EROSION AND SEDIMENT CONTROLS (4.2 2.a.(1)(a)-(f))**

(Check all that apply)

- **Stabilization Practices (See Detail Plan Sheets)**
  - Temporary or Permanent Seeding
  - Sodding
  - Planting
  - Mulching (Straw or Cellulose Fiber)
  - Erosion Control Blankets or Mats
  - Vegetation Buffer Strips
  - Roughened Surface (e.g. tracking)
  - Gabions-Gabion Mattress
  - Other

### ➤ **Structural Temporary Erosion and Sediment Controls**

- Silt Fence
- Straw Bale Check
- Temporary Berm
- Temporary Slope Drain
- Straw Wattles or Rolls
- Diversion Channels/Swales
- Channel Liners (TRM)
- Stone Rip Rap Sheet
- Rock Check Dams
- Sediment Traps/Basins
- Inlet Protection
- Outlet Protection
- Surface Inlet Protection
- Curb Inlet Protection
- Stabilized Construction Entrances
- Other

### ➤ **Wetland Avoidance**

Will construction and/or erosion and sediment controls impinge on regulated wetlands? Yes  No  If yes, the structural and erosion and sediment controls have been included in the total project wetland impacts and have been included in the 404 permit process with the USACE.

### ➤ **Storm Water Management (4.2 2.b., (1) and (2))**

Storm water management will be handled by temporary controls outlined in Section 3 above, and any permanent controls needed to meet permanent storm water management needs in the post construction period. Permanent controls will be shown on the plans and noted as permanent.

### ➤ **Other Storm Water Controls (4.2 2.c., (1) and (2))**

- **Waste Disposal**  
All liquid waste materials will be collected and stored in sealed metal containers approved by the project engineer. All trash and construction debris from the site will be deposited in the approved containers. Containers will be serviced as necessary, and the trash will be hauled to an approved disposal site or licensed landfill. All onsite personnel will be instructed in the proper procedures for waste disposal, and notices stating proper practices will be posted in the field office. The general contractor's representative responsible for the conduct of work on the site will be responsible for seeing waste disposal procedures are followed.
- **Hazardous Waste**  
All hazardous waste materials will be disposed of in a manner specified by local or state regulations or by the manufacturer. Site personnel will be instructed in these practices, and the individual designated as the contractor's on-site representative will be responsible for seeing that these practices are followed.
- **Sanitary Waste**  
Portable sanitary facilities will be provided on all construction sites. Sanitary waste will be collected from the portable units in a timely manner by a licensed waste management contractor or as required by any local regulations.

### ❖ **Maintenance and Inspection (4.2 3. and 4.2 4.)**

#### ➤ **Maintenance and Inspection Practices**

- Inspections will be conducted at least one time per week and after a storm event of 0.50 inches or greater.
- All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report.

### ➤ **Maintenance and Inspection Practices(Continued)**

- Silt fence will be inspected for depth of sediment and for tears in order to ensure the fabric is securely attached to the posts and that the posts are well anchored. Sediment buildup will be removed from the silt fence when it reaches 1/3 of the height of the silt fence.
- Sediment basins and traps will be checked. Sediment will be removed when depth reaches approximately 50 percent of the structure's capacity, and at the conclusion of the construction.
- Check dams will be inspected for stability. Sediment will be removed when depth reaches 1/2 the height of the dam.
- All seeded areas will be checked for bare spots, washouts, and vigorous growth free of significant weed infestations.
- Inspection and maintenance reports will be prepared on form DOT 298 for each site inspection, this form will also be used to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents.
- The SDDOT Project Engineer and contractor's site superintendent are responsible for inspections. Maintenance, repair activities are the responsibility of the contractor. The SDDOT Project Engineer will complete the inspection and maintenance reports and distribute copies per the distribution instructions on DOT 298.

### ❖ **Non-Storm Water Discharges (3.0)**

The following non-storm water discharges are anticipated during the course of this project (check all that apply).

- Discharges from water line flushing.
- Pavement wash-water, where no spills or leaks of toxic or hazardous materials have occurred.
- Uncontaminated ground water associated with dewatering activities.

### ❖ **Materials Inventory (4.2. 2.c.(2))**

The following materials or substances are expected to be present on the site during the construction period. These materials will be handled as noted under the headings "EROSION AND SEDIMENT CONTROLS" and "SPILL PREVENTION" (check all that apply).

- Concrete and Portland Cement
- Detergents
- Paints
- Metals
- Bituminous Materials
- Petroleum Based Products
- Cleaning Solvents
- Wood
- Cure
- Texture
- Chemical Fertilizers
- Other

# SWPPP

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	8	23
SWPPP	6/7/2017	

## ❖ (4.2 2.c.(2))

### ➤ Material Management Spill Prevention

#### ▪ Housekeeping

- Only needed products will be stored on-site by the contractor.
- Except for bulk materials the contractor will store all materials under cover and in appropriate containers.
- Products must be stored in original containers and labeled.
- Material mixing will be conducted in accordance with the manufacturer's recommendations.
- When possible, all products will be completely used before properly disposing of the container off site.
- The manufacturer's directions for disposal of materials and containers will be followed.
- The contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
- Dust generated will be controlled in an environmentally safe manner.
- Vegetation areas not essential to the construction project will be preserved and maintained as noted on the plans.

#### ▪ Hazardous Materials

- Products will be kept in original containers unless the container is not resealable.
- Original labels and material safety data sheets will be retained in a safe place to relay important product information.
- If surplus product must be disposed of, manufacturer's label directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, de-greasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any storm water system or storm water treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, and mixer washout waters will be collected on site and managed to prevent contamination of storm water runoff.

### ➤ Product Specific Practices (6.8)

#### ▪ Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

#### ▪ Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to storm water. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

### ➤ Product Specific Practices (6.8) (Continued)

#### ▪ Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the manufacturer's instructions and any applicable state and local regulations.

#### ▪ Concrete Trucks

Contractors will provide designated truck washout areas on the site. These areas must be self contained and not connected to any storm water outlet of the site. Upon completion of construction washout areas will be properly stabilized.

### ➤ Spill Control Practices (4.2 2 c.(2))

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill clean up will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as booms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for clean up purposes.
- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator. The contractor is responsible for ensuring that the site superintendent has had appropriate training for hazardous materials handling, spill management, and cleanup.

### ➤ Spill Response (4.2 2 c.(2))

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into storm water runoff and conveyance systems. If the release has impacted on-site storm water, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens storm water or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.
- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.

### ➤ Spill Response (4.2 2 c.(2)) (Continued)

- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the contractor at the site.
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to remove the material causing the sheen. The contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.
- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SD DENR.
- Personnel with primary responsibility for spill response and clean up will receive training by the contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials.
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

### ❖ Spill Notification

In the event of a spill, the contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures:

- A reportable spill is a quantity of 25 gallons or more or any spill of oil which: 1) violates water quality standards, 2) produces a "sheen" on a surface water, or 3) causes a sludge or emulsion must be reported immediately to the National Response Center .
- Any spill of oil or hazardous substance to waters of the state must be reported immediately by telephone to the SD DENR.

### ❖ Construction Changes (4.4)

When changes are made to the construction project that will require alterations in the temporary erosion controls of the site, the Storm Water Pollution Prevention Plan (SWPPP) will be amended to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP plan (DOT 298) and drawings to reflect the needed changes. Copies of changes will be routed per DOT 298. Copies of forms and the SWPPP will be retained in a designated place for review over the course of the project.



# SWPPP

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	9	23
SWPPP	6/7/2017	

## ❖ CERTIFICATIONS

### ➤ Certification of Compliance with Federal, State, and Local Regulations

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

### ➤ City of Yankton, South Dakota

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

\_\_\_\_\_  
Authorized Signature. (See the General Permit, Section 6.7.1.C.)

### ➤ Prime Contractor

This section is to be executed by the General Contractor after the award of the contract and at least 15 days prior to the beginning of construction. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

\_\_\_\_\_  
Authorized Signature. (See the General Permit, Section 6.7.1.a .or b.)

## ❖ CONTACT INFORMATION

### ➤ Contractor Information:

- Prime Contractor Name:
- Contractor Contact Name:
- Address:
- Address:
- City:            State:            Zip:
- Office Phone:            Field:            Cell:            Fax:

### ➤ City Engineer

- Name: Brad Moser
- Business Address: 416 Walnut Street
- Job Office Location
- City: Yankton State: SD Zip: 57078
- Office Phone: 605 668-5255 Field:            Cell:            Fax:

### ➤ SD DENR Contact Spill Reporting

- Business Hours Monday-Friday (605) 773-3296
- Nights and Weekends (605) 773-3231

### ➤ SD DENR Contact for Hazardous Materials.

- (605) 773-3153



### ➤ National Response Center Hotline

- (800) 424-8802.

CEDAR STREET REMOVALS

CEDAR STREET CALMER LAYOUT

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	10	23
CEDAR STREET CALMERS		6/7/2017



- 1. **NW QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 52 SY  
 CONCRETE FILLET REMOVAL 22 SY  
 8" CONCRETE PAVING REMOVAL 195 SY  
 CURB REMOVAL 47 LF
- 3. **SW QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 48 SY  
 CONCRETE FILLET REMOVAL 26 SY  
 8" CONCRETE PAVING REMOVAL 88 SY  
 CURB REMOVAL 20 LF

- 2. **NE QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 72 SY  
 CONCRETE FILLET REMOVAL 26 SY  
 8" CONCRETE PAVING REMOVAL 200 SY  
 CURB REMOVAL 43 LF
- 4. **SE QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 17 SY  
 CONCRETE FILLET REMOVAL 28 SY  
 8" CONCRETE PAVING REMOVAL 100 SY  
 CURB REMOVAL 32 LF


REMOVAL AREA

- 1. **NW QUADRANT**  
 6" CONC. SIDEWALK 645  
 6" COLORED CONC. SIDEWALK 495 SF  
 8" CONCRETE FILLET SECTION 170 SF  
 8" CONCRETE PAVING 131 SY  
 B68 CURB 71 LF
- 3. **SW QUADRANT**  
 6" CONC. SIDEWALK 306 SF  
 6" COLORED CONC. SIDEWALK 298 SF  
 8" CONCRETE FILLET SECTION 150 SF  
 8" CONCRETE PAVING 72 SY  
 B68 CURB 38 LF

- 2. **NE QUADRANT**  
 6" CONC. SIDEWALK 660 SF  
 6" COLORED CONC. SIDEWALK 685 SF  
 8" CONCRETE FILLET SECTION 182 SF  
 8" CONCRETE PAVING 128 SY  
 B68 CURB 87 LF
- 4. **SE QUADRANT**  
 6" CONC. SIDEWALK 256 SF  
 6" COLORED CONC. SIDEWALK 389  
 8" CONCRETE FILLET SECTION 150 SF  
 8" CONCRETE PAVING 68 SY  
 B68 CURB 35 LF


# CEDAR STREET CALMER LAYOUT

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	11	23
CEDAR STREET CALMERS		6/7/2017




**LEGEND**

- LT — LT — LT — LONGITUDINAL CONSTRUCTION JOINT WITH TIE BARS  
SEE DETAIL SHEET (PLATE #380.10 & 380.11)
- L — L — L — LONGITUDINAL CONSTRUCTION JOINT WITHOUT TIE BARS  
SEE DETAIL SHEET (PLATE #380.12)
- TRANSVERSE CONTRACTION JOINT  
SEE DETAIL (PLATE #380.03)




# DOUGLAS AVE. REMOVALS




- |   |  |
|---|--|
| <p><b>1. NW QUADRANT</b><br/>         CONCRETE SIDEWALK REMOVAL 75 SY<br/>         CONCRETE FILLET REMOVAL 23 SY<br/>         8" CONCRETE PAVING REMOVAL 256 SY<br/>         CURB REMOVAL 48 LF</p> <p><b>3. SW QUADRANT</b><br/>         CONCRETE SIDEWALK REMOVAL 16 SY<br/>         CONCRETE FILLET REMOVAL 22 SY<br/>         8" CONCRETE PAVING REMOVAL 148 SY<br/>         4" ASPHALT PAVING REMOVAL 300 SY<br/>         CURB REMOVAL 88 LF</p> | <p><b>2. NE QUADRANT</b><br/>         CONCRETE SIDEWALK REMOVAL 71 SY<br/>         CONCRETE FILLET REMOVAL 23 SY<br/>         8" CONCRETE PAVING REMOVAL 258 SY<br/>         CURB REMOVAL 46 LF</p> <p><b>4. SE QUADRANT</b><br/>         CONCRETE SIDEWALK REMOVAL 13 SY<br/>         CONCRETE FILLET REMOVAL 19 SY<br/>         8" CONCRETE PAVING REMOVAL 139 SY<br/>         4" ASPHALT PAVING REMOVAL 190 SY<br/>         CURB REMOVAL 162 LF</p> |
|---|--|

# DOUGLAS AVE. CALMER LAYOUT

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	12	23
DOUGLAS AVE. CALMERS		6/7/2017



- |   |   |
|---|---|
| <p><b>1. NW QUADRANT</b><br/>         6" CONC. SIDEWALK 775 SF<br/>         6" COLORED CONC. SIDEWALK 557 SF<br/>         8" CONCRETE FILLET SECTION 248 SF<br/>         8" CONCRETE PAVING 138 SY<br/>         B68 CURB 104 LF</p> <p><b>3. SW QUADRANT</b><br/>         6" CONC. SIDEWALK 371 SF<br/>         6" COLORED CONC. SIDEWALK 579 SF<br/>         8" CONCRETE FILLET SECTION 246 SF<br/>         8" CONCRETE PAVING 333 SY<br/>         B68 CURB 136 LF</p> | <p><b>2. NE QUADRANT</b><br/>         6" SIDEWALK 683 SF<br/>         6" COLORED CONC. SIDEWALK 659 SF<br/>         8" CONCRETE FILLET SECTION 244 SF<br/>         8" CONCRETE PAVING 142 SY<br/>         B68 CURB 104 LF</p> <p><b>4. SE QUADRANT</b><br/>         6" CONC. SIDEWALK 1160 SF<br/>         6" COLORED CONC. SIDEWALK 1020 SF<br/>         8" CONCRETE FILLET SECTION 228 SF<br/>         8" CONCRETE PAVING 313 SY<br/>         B68 CURB 215 LF</p> |
|---|---|



# DOUGLAS AVE. CALMER LAYOUT & STORM SEWER LAYOUT

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	13	23
DOUGLAS AVE. CALMERS		6/7/2017

**NOTE:**  
STA. 1+26 - 60' LT.  
LIGHT POLE TO BE MOVED

1+18.2-73.0' LT. TO 1+18.2-63.7' LT.  
INSTALL 8 L.F. OF 18" RCP @ 0.4%  
CORE EXISTING INLET AT 1+18.2 - 63.7' LT.  
SEAL TOP OF INLET WALLS & COVER WITH  
REINFORCED CONCRETE LID

1+18.2 - 73.0' LT.  
INSTALL TYPE B INLET  
TO ELEV. = 1194.72  
INV. OUT = 1190.27  
(FIELD VERIFY ELEVATIONS)


SAW CUT & INSTALL  
#5X24" BARS 4' O.C.

SAW CUT & INSTALL  
#5X24" BARS 4' O.C.

### LEGEND

- LT — LT — LT — LONGITUDINAL CONSTRUCTION JOINT WITH TIE BARS  
SEE DETAIL SHEET (PLATE #380.10 & 380.11)
- L — L — L — LONGITUDINAL CONSTRUCTION JOINT WITHOUT TIE BARS  
SEE DETAIL SHEET (PLATE #380.12)
- TRANSVERSE CONTRACTION JOINT  
SEE DETAIL (PLATE #380.03)

SCALE: 1" = 15'



0+24.5 - 45' RT.  
INSTALL 2'X2' AREA DRAIN  
2.3' FROM INVERT TO TOP OF DRAIN  
(SEE DETAIL ON PAGE 23)



0+24.5 - 38' RT.  
INSTALL 2'X2' JUNCTION BOX  
& 2'X2' REINFORCED CONC. LID  
2.6' FROM INVERT TO TOP OF MH LID  
SAW CUT EXISTING 18" RCP STORM PIPE

0+24.5 - 38' RT. TO 0+24.5 - 45' RT.  
INSTALL 8 LF OF 15" RCP

# CAPITAL ST. REMOVALS

# CAPITAL STREET CALMER LAYOUT

PROJECT	2017-012	SHEET NO.	14	TOTAL SHEETS	23
CAPITAL ST. CALMERS			6/7/2017		



- 1. **NW QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 68 SY  
 CONCRETE FILLET REMOVAL 14 SY  
 8" CONCRETE PAVING REMOVAL 155 SY  
 CURB REMOVAL 40 LF
- 3. **SW QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 70 SY  
 CONCRETE FILLET REMOVAL 13 SY  
 8" CONCRETE PAVING REMOVAL 133 SY  
 4" ASPHALT PAVING REMOVAL 380 SY  
 CURB REMOVAL 80 LF

- 2. **NE QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 61 SY  
 CONCRETE FILLET REMOVAL 14 SY  
 8" CONCRETE PAVING REMOVAL 155 SY  
 CURB REMOVAL 44 LF
- 4. **SE QUADRANT**  
 CONCRETE SIDEWALK REMOVAL 45 SY  
 CONCRETE FILLET REMOVAL 13 SY  
 8" CONCRETE PAVING REMOVAL 142 SY  
 4" ASPHALT REMOVAL 210 SY  
 CURB REMOVAL 32 LF

- 1. **NW QUADRANT**  
 6" CONC. SIDEWALK 630 SF  
 6" COLORED CONC. SIDEWALK 512 SF  
 8" CONCRETE FILLET SECTION 175 SF  
 8" CONCRETE PAVING 89 SY  
 B68 CURB 70 LF
- 3. **SW QUADRANT**  
 6" CONC. SIDEWALK 1000 SF  
 6" COLORED CONC. SIDEWALK 580 SF  
 8" CONCRETE FILLET SECTION 145 SF  
 8" CONCRETE PAVING 268 SY  
 B68 CURB 160 LF

- 2. **NE QUADRANT**  
 6" CONC. SIDEWALK 560 SF  
 6" COLORED CONC. SIDEWALK 610 SF  
 8" CONCRETE FILLET SECTION 168 SF  
 8" CONCRETE PAVING 89 SY  
 B68 CURB 70 LF
- 4. **SE QUADRANT**  
 6" CONC. SIDEWALK 600 SF  
 6" COLORED CONC. SIDEWALK 508 SF  
 8" CONCRETE FILLET SECTION 175 SF  
 8" CONCRETE PAVING 277 SY  
 B68 CURB 60 LF







ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT	VARIABLE
* CLASS M6 CONCRETE	CUYDS	0.27	0.32V
REINFORCEMENT-CONC. MASONRY	LBS	28	---

\* CONSTANT SHALL BE REDUCED FOR THE APPROPRIATE PIPE OR COMBINATION OF PIPES, THUS; 12" DIA.=0.03 C.Y., 15" DIA.=0.04 C.Y., 18" DIA.=0.05 C.Y., 24" DIA.=0.09 C.Y.


FRAME & GRATE WITH ADJUSTABLE CURB BOX - NEENAH R-3067 WITH TYPE "V" GRATE OR ENGINEER APPROVED EQUAL



MAX. 4" OF CONCRETE MASONRY UNITS AND/OR GROUT FOR ADJUSTMENT





REVISED: DECEMBER 1995

SPECIFICATION REFERENCE NO. 460		CITY OF SIOUX FALLS ENGINEERING DIVISION STANDARD STORM SEWER INLET TYPE BI	PLATE NUMBER 460.07
--	---	--	---------------------------

TOLERANCES IN DIMENSIONS

Diameter:  $\pm 1.5\%$  for 24" Dia. or less and  $\pm 1\%$  or  $\frac{3}{8}$ " whichever is more for 27" Dia. or greater.  
 Diameters at Joints:  $\pm 3/16$ " for 30" Dia. or less and  $\pm 1/4$ " for 36" or greater.  
 Length of joint (J):  $\pm 1/4$ ".  
 Wall thickness (T): not less than design T by more than 5% or  $\frac{3}{16}$ ", whichever is greater.  
 Laying length: shall not underrun by more than  $\frac{1}{2}$ ".



LONGITUDINAL SECTION

END VIEW

GENERAL NOTES:

Construction of R.C.P. shall conform to the requirements of Section 990 of the Standard Specifications for Roads and Bridges.

Not more than 2 four foot sections shall be permitted near the ends of any culvert. Four foot lengths shall be used only to secure the required length of culvert.

Diam. (in.)	Approx. Wt. /Ft. (lb.)	T (in.)	J (in.)	D1 (in.)	D2 (in.)	D3 (in.)	D4 (in.)
12	92	2	1 3/4	13 1/4	13 5/8	13 1/8	14 1/4
15	127	2 1/4	2	16 1/2	16 7/8	17 1/4	17 5/8
18	168	2 1/2	2 1/4	19 5/8	20	20 3/8	20 3/4
21	214	2 3/4	2 1/2	22 7/8	23 1/4	23 3/4	24 1/8
24	265	3	2 3/4	26	26 3/8	27	27 3/8
27	322	3 1/4	3	29 1/4	29 5/8	30 1/4	30 5/8
30	384	3 1/2	3 1/4	32 3/8	32 3/4	33 1/2	33 7/8
36	524	4	3 3/4	38 3/4	39 1/4	40	40 1/2
42	685	4 1/2	4	45 1/8	45 5/8	46 1/2	47
48	867	5	4 1/2	51 1/2	52	53	53 1/2
54	1070	5 1/2	4 1/2	57 7/8	58 3/8	59 3/8	59 7/8
60	1296	6	5	64 1/4	64 3/4	66	66 1/2
66	1542	6 1/2	5 1/2	70 5/8	71 1/8	72 1/2	73
72	1810	7	6	77	77 1/2	79	79 1/2
78	2098	7 1/2	6 1/2	83 3/8	83 3/8	85 5/8	86 1/8
84	2410	8	7	89 3/4	90 1/4	92 1/8	92 5/8
90	2740	8 1/2	7	95 3/4	96 1/4	98 1/8	98 5/8
96	2950	9	7	102 1/8	102 5/8	104 1/2	105
102	3075	9 1/2	7 1/2	109	109 1/2	111 1/2	112
108	3870	10	7 1/2	115 1/2	116	118	118 1/2

March 31, 2000

<b>S D D T</b>	<b>REINFORCED CONCRETE PIPE</b>	PLATE NUMBER 450.01
	Published Date: 1st Qtr. 2012	Sheet 1 of 1



### 30" CONCRETE CURB AND GUTTER N.T.S



1/2" Preformed Expansion Joint Fillers shall be placed, Transversely in the Curb & Gutter as follows:

- (1) At each junction of Radius return Curb & Gutter and the Curb & Gutter which is parallel to the project centerline.
- (2) At each junction with existing Concrete Curb or Concrete Curb & Gutter
- (3) At each junction with existing sidewalk, to the depth of the sidewalk.
- (4) At a maximum of 195 L.F. apart, measured along the face of the Curb & Gutter.

1/2" Preformed Expansion Joint Filler shall be placed, Longitudinally, along the backface of the Curb, to the depth of the sidewalk, where such backface of Curb is adjacent to an existing Concrete Sidewalk.


Weakened Plane Joints shall be constructed at Approx. 10' intervals. The joints shall be constructed to a minimum depth of one inch by scoring with a tool which coincide with pavement joints leave the corners rounded and insure a free movement of the Concrete at the joint.

TYPE	T1 INCHES	CU. YD PER LIN. FT.
B66	6"	0.055
B67	7"	0.063
B68	8"	0.071
B68.5	8.5"	0.074
B69	9"	0.078
B69.5	9.5"	0.082
B610	10"	0.086
B610.5	10.5"	0.090
B611	11"	0.094
B611.5	11.5"	0.098
B612	12.0"	0.102



**TYPICAL FILLET SECTION**  
N.T.S.

All Fillet sections to contain fiber mesh reinforced concrete.



**GENERAL NOTES:**

The saw cut to control cracking shall be a minimum of 1/4 the thickness of the pavement.  
All hot poured elastic joint sealer material spilled on the surface of the concrete pavement shall be removed as soon as the material has cooled. The extent of removal of material shall be to the satisfaction of the Engineer. All costs for removal of the spilled joint sealer material shall be borne by the Contractor.

December 23, 2007

Published Date: 4th Qtr. 2009

**S  
D  
D  
O  
T**


**PCC PAVEMENT TRANSVERSE CONTRACTION  
JOINT WITH OR WITHOUT DOWEL BAR ASSEMBLY**

PLATE NUMBER  
380.03

Sheet 1 of 1

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	18	23
Details	6/7/2017	

**LONGITUDINAL CONSTRUCTION JOINT WITH TIE BARS  
(DRILLED IN BARS)**



**GENERAL NOTES:**

The tie bars shall be embedded a minimum depth of 9 inches into the in place PCC pavement and anchored with an epoxy resin adhesive.


No.5 epoxy coated deformed tie bars shall be spaced 48" center to center for a female keyway or 30" center to center for a vertical face and male keyway. The keyway shown above is a female keyway.

The tie bars shall be placed a minimum of 15 inches from existing transverse contraction joints.

The keyway is optional and is not required. When concrete pavement is formed and a keyway is provided, a metal recess strip shall be used. When concrete pavement is slip formed, a metal recess strip is not required.

The term "In Place PCC Pavement" in the above drawing indicates that the in place PCC pavement was placed on a previous project or current project.

**LONGITUDINAL CONSTRUCTION JOINT WITH TIE BARS  
(INSERTED OR FORMED IN BARS)**



**GENERAL NOTES:**

No.5 epoxy coated deformed tie bars shall be spaced 48" center to center for a female keyway or 30" center to center for a vertical face and male keyway. The keyway shown above is a female keyway.

The tie bars shall be placed a minimum of 15 inches from existing transverse contraction joints.

The keyway is optional and is not required. When concrete pavement is formed and a keyway is provided, a metal recess strip shall be used. When concrete pavement is slip formed, a metal recess strip is not required.

The term "In Place PCC Pavement" in the above drawing indicates that the in place PCC pavement was placed on the current project.

September 14, 2001

Published Date: 4th Qtr. 2007


S  
D  
D  
O  
T

**PCC PAVEMENT LONGITUDINAL  
JOINTS WITH TIE BARS**

PLATE NUMBER  
380.10

Sheet 1 of 2

**SAWED LONGITUDINAL JOINT WITH TIE BARS  
(POURED MONOLITHICALLY)**



**GENERAL NOTES:**

No.5 epoxy coated deformed tie bars shall be spaced 48 inches center to center.

The tie bars shall be placed a minimum of 15 inches from the existing transverse contraction joints.

The first saw cut to control cracking shall be a minimum of 1/3 the thickness of the pavement. Additional sawing for widening the saw cut to provide the width for the installation of the hot poured elastic joint sealer will be necessary.

September 14, 2001

Published Date: 4th Qtr. 2007


S  
D  
D  
O  
T

**PCC PAVEMENT LONGITUDINAL  
JOINTS WITH TIE BARS**

PLATE NUMBER  
380.10

Sheet 2 of 2

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	19	23
Details		6/7/2017



**GENERAL NOTES:**


No. 5 epoxy coated deformed tie bars shall be spaced 48" center to center. The keyway shown above is a female keyway.

The tie bars shall be placed a minimum of 15 inches from existing transverse contraction joints.

The keyway is optional and is not required. When concrete pavement is formed and a keyway is provided, a metal recess strip shall be used. When concrete pavement is slip formed, a metal recess strip is not required.

The transverse contraction joints in the concrete gutter or concrete curb and gutter shall be placed at each mainline PCC pavement transverse contraction joint. The transverse contraction joints in the concrete gutter or the concrete curb and gutter shall be 1/2" deep if formed in fresh concrete using a suitable grooving tool. If a saw is used to cut the transverse contraction joints, then the depth of the joint shall be at least 1/4 the thickness of the concrete gutter or concrete curb and gutter.

The term "In Place Gutter or Curb and Gutter" in the above drawing indicates that the in place concrete gutter and concrete curb and gutter was placed on the current project.



**GENERAL NOTES:**


The mainline curb and gutter may be placed monolithically with the PCC pavement. If this method of construction is used, the tie bars and the sawed joint between the curb and gutter and the PCC pavement shall be eliminated.

The gutter or curb and gutter shall be sawed transversely at each mainline transverse contraction joint. The transverse contraction joints in the gutter or curb and gutter shall be sawed and sealed same as the transverse contraction joints in the PCC pavement.

The slope of the gutter shall be the slope designated for the type of gutter or curb and gutter to be constructed. The bottom slope of the gutter or curb and gutter shall be constructed at the same slope as the mainline concrete pavement.

September 14, 2005


<b>S D D O T</b>	<b>PCC PAVEMENT LONGITUDINAL CONSTRUCTION JOINTS WITH CONCRETE GUTTER OR CONCRETE CURB AND GUTTER</b>	PLATE NUMBER <b>380.11</b>
	<i>Published Date: 4th Qtr. 2007</i>	Sheet 1 of 1



**GENERAL NOTES:**

When concrete pavement is formed and a keyway is provided, a metal recess strip shall be used. When concrete pavement is slip formed, a metal recess strip is not required.

The term "In Place PCC Pavement" in the above drawing indicates that the in place PCC pavement was placed on the current project.





**GENERAL NOTE:**

The term "In Place PCC Pavement" in the above drawing indicates that the in place PCC pavement was placed on a previous project.

September 14, 2001


<b>S D D O T</b>	<b>PCC PAVEMENT LONGITUDINAL JOINTS WITHOUT TIE BARS</b>	PLATE NUMBER <b>380.12</b>
	<i>Published Date: 4th Qtr. 2007</i>	Sheet 1 of 2

PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	20	23
Details	6/7/2017	





PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	22	23
Details	6/7/2017	




**GENERAL NOTES:**

- The grate and curb and gutter shown are for illustrative purposes only.
- The sediment control at inlet with frame and grate shall be placed at locations stated in the plans or at locations determined by the Engineer.
- The filter fabric shall be the type specified in the plans.
- The filter fabric shall be placed in the inlet opening prior to placing the grate. Approximately 18 inches of excess filter fabric shall be wrapped around the 2"x4" and stapled securely to the 2"x4" after the grate has been placed.
- The Contractor shall inspect and maintain the sediment control device once every week and within 24 hours after every rainfall event. The Contractor shall maintain the sediment control device by removing accumulated sediment and replacing torn filter fabric with new filter fabric.
- The removed sediment shall be placed at a location away from the drop inlet where the sediment will not be washed back into the drop inlet or other storm sewer system.
- All costs for furnishing, installing, inspecting, maintaining, removing, and replacing the sediment control device at the inlet including labor, equipment, and materials shall be incidental to the contract unit price per each for "Sediment Control at Inlet with Frame and Grate".

September 14, 2005

Published Date: 1st Qtr. 2012	S D D O T	SEDIMENT CONTROL AT INLETS WITH FRAMES AND GRATES	PLATE NUMBER 734.10
			Sheet 1 of 1



**INLET PROTECTION**




**DEFINITION:**

A SEDIMENT FILTER OR AN EXCAVATED IMPOUNDING AREA AROUND A STORM DRAIN DROP INLET OR CURB INLET.

**PURPOSES:**

TO REDUCE SEDIMENT FROM ENTERING STORM DRAINAGE SYSTEMS PRIOR TO PERMANENT STABILIZATION OF DISTURBED AREAS.




FILTER FABRIC SHALL CONFORM TO SECTION 831 OF SDDOT STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES, LATEST EDITION.

REVISED: JUNE 2000

SPECIFICATION REFERENCE NO. 734	CITY OF SIOUX FALLS ENGINEERING DIVISION GRAVEL/CONCRETE BLOCK DROP INLET SEDIMENT FILTER	PLATE NUMBER 734.19
---------------------------------	---	---------------------


PROJECT	SHEET NO.	TOTAL SHEETS
2017-012	23	23
Details	6/7/2017	



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT	VARIABLE
* CLASS M6 CONCRETE	CUYDS	0.17	0.19V
REINFORCEMENT-CONC. MASONRY	LBS	16	---

\* CONSTANT SHALL BE REDUCED FOR THE APPROPRIATE PIPE OR COMBINATION OF PIPES, THUS; 12" DIA.=--0.03 C.Y., 15" DIA.=--0.04 C.Y., 18" DIA.=--0.05 C.Y.

REVISED: DECEMBER 1995

SPECIFICATION REFERENCE NO. 460		CITY OF SIOUX FALLS ENGINEERING DIVISION 2' X 2' CATCH BASIN WITH SURFACE DRAIN	PLATE NUMBER 460.08
--	---	--	---------------------------