

**ADDENDUM NO. 2**


Dated: March 9, 2021

Plans and Specifications for: **Spruce Street from 4<sup>th</sup> Street to 6<sup>th</sup> Street – Street & Utility**

Bids Due: 3:00 PM  
March 12, 2021  
City Finance Officer  
P.O. Box 176  
Yankton, SD 57078

Contact Person: Bradley Moser  
Civil Engineer  
P.O. Box 176  
Yankton, SD 57078  
(605) 668-5255

The original plans and specifications are hereby amended by this Addendum. Bidders shall acknowledge receipt of this addendum by noting the addendum number and date on the space provided on the Bid Form. Bidders who distribute these specifications to subcontractors or suppliers are responsible for the distribution of the information contained herein to either the subcontractor or supplier.

Issued By   
Bradley C. Moser, Civil Engineer

1. The attached, is a revised Page 5, for the “Measurement and Payment” section, of the specifications. The City of Yankton will be supplying the new fire hydrants.

This does NOT affect the bid proposal form. Your unit price for bid item #50 – “Install Fire Hydrant” is for installation of the hydrants, as per the detail in the construction plans.

**Granular Material for Watermain:** – **Per linear foot** unit price shall be full compensation for furnishing and installing granular material under, around and above the watermain, measured to the nearest whole linear foot.

**Install Fire Hydrants:** - **Per each** unit price shall be full compensation for installation of city supplied hydrants, in the proper location, with thrust restraint, poly wrap and crushed rock drain field.

**Removal Fire Hydrant:** - **Per each** unit price shall be full compensation for excavating, removing, backfilling, and salvaging a fire hydrant. The salvaged hydrant shall remain on the project site until removed by the City of Yankton.

**Cut and Tie to Existing Watermain:** – **Per each** unit price shall be full compensation for excavation and backfilling, cutting the existing watermain, draining the pipe and dewatering as necessary, furnishing all labor necessary to do the work and to contact the affected water users. These items will be counted as noted on the plans. Where a single valve, plug, cap, etc. is cut in, the cut and tie to existing watermain bid item will only be paid for once.

**Water Service Line Reconnection:** - **Per each** includes furnishing and installing service saddle, corporation stop, pipe, pipe fittings and sleeves as are necessary to reconnect existing services to new main. Includes temporary service arrangements if necessary.

**Traffic Control:** - **Per unit** price is for furnishing, installing, and maintaining the traffic control devices shown on the plans. All traffic control devices and locations shall conform to the latest edition of the "Manual on Uniform Traffic Control Devices". The unit price shall be full compensation for re-locations or re-installing any sign or device during the duration of the project as directed by the Engineer.

**Traffic Control Misc.:** - **Lump sum** unit price is for furnishing, installing, and maintaining the small barricades, drums, cones, etc. at all other areas of the project that are not shown on the plans. All traffic control devices and locations shall conform to the latest edition of the "Manual on Uniform Traffic Control Devices." The lump sum price shall be full compensation for any re-location or re-installing of any device due to change in traffic patterns, scheduling, or as deemed necessary by the Engineer through the duration of the project.

**Portland Cement Concrete Pavement:** - **Per square yard** unit price called for by the proposal includes subgrade preparation and fine grading, furnishing materials, reinforcing, placement, finishing, control joints, sawing existing pavement as shown on drawings, sealing joints, protecting existing concrete from damage, curing compound, expansion joint material, traffic control and barricading, and backfill after forms have been removed.

**Concrete Fillet Section and/or Valley Gutter:** - **Per square foot** unit price will be for fillets or valley gutter without reinforcing steel. Concrete is to contain fiber mesh as specified. Unit price includes all general concrete work items. Curb attached to fillets is considered part of fillet and no separate measurement will be made for curb attached to fillet.

**Concrete Curb & Gutter:** - **Per linear foot** unit price includes general items for concrete pavement placement for the type and style stipulated and shall be full compensation for measured in place curb and gutter consisting of Class M-6 Concrete (curved and straight sections if not separated on bid form).